

No. 6.—DAM OF BIG BRANCH RESERVOIR.

Cubic yards.		Price. Cts.	Cost.	Total cost.
21814	Gravel removed from foundation,	18	\$3,926 52	
117082	Embankment,	24	28,099 68	
37392	Puddling of puddle dyke,	40	14,956 80	
1670	Soiling of lower slope,	25	417 50	47,400 00
Perches.				9,424 00
4712	Paving on upper slope,	200		71,296 00
8662	Masonry of culvert of feeder,	800		6,000 00
	Waste weir and waste lead,			
	Gauge of culvert—gauge rods—sheath for do,—and house on top of embankment,			5,000 00
	Pumping apparatus,			4,000 00
				<u>\$143,120 00</u>